# UBTECH UBT43S Silence Hydraulic Hammer / Rock Concrete Breaker Suit Telehandlers

## Details

| | |
|---|---|
| **Price:** | $9,750 Ex. GST |
| **Dealer Stock #:** | ATTUBT |
| **New / Used:** | Dealer New |



## Seller Details

| | |
|---|---|
| **Name:** | Southern Tool + Equipment |
| **Phone:** | (07) 3177 7347 |
| **State:** | QLD |
| **Suburb:** | DARRA |
| **Postcode:** | 4076 |

## Description

UBTECH UBT43S Silence Hydraulic Hammer / Rock Concrete Breaker Suit Telehandlers ATTUBT Rockbreakers / Tele handler mounting frame WORK READY-----ONLY $9,750+GST Come with 5 Years Warranty on Main Frame & 12 Months Factory Parts Warranty. **Factory warranty does not cover everyday wear parts, consumables or everyday maintenance issues. All hammers are WORK READY with no surprise costs when it comes to fitting your hammer to your machine, Come complete with moil, hoses and head bracket installed. Hydraulic hoses supplied are 1.5 m standard with screw-in fittings. Simply attach to the excavator and begin work with your breaker pre-gassed, flow and pressure tested, and fully adjusted to suit your machine. UBT43S, Suit CAT, BOBCAT Telehandlers . Gross Weight----------380kg (without Pick up frame, Moil, Pins, Hoses), . Required Oil Flow------40 to 80L/min, . Operating Pressure----100 to 130 bar (1450 to 1885 psi), . Setting Pressure--------170 bar (2465 psi), . Tool Shank Diameter--75mm (2.95 inches), . Impact Rate----------450 to 900 bpm, . Hose Diameter---------12.7mm (1/2 inch). All units come complete with: . 1 x Mounting Bracket . 2 x Mounting Pins . 2 x Hydraulic Hoses . 1 x Tool Kit . 1 x Recharge Kit . 1 x Full Seal Kit . 1 x Chisel Attachment . 1 x Moil Attachment

© 2015-2026 TruckDealers.com.au. All Rights Reserved.

## Product Details

| | |
|---|---|
| **Price** | $9,750 |
| **Type** | Dealer New |
| **Model** | UBT43S |
| **Registration Date** | N/A |

© 2015-2026 TruckDealers.com.au. All Rights Reserved.




















© 2015-2026 TruckDealers.com.au. All Rights Reserved.